



Asbestos Register

Blue Mountains City Council maintains asbestos registers (“registers”) and asbestos management plans (“plans”) relating to each of the buildings owned or occupied by the Council. The registers and plans record information about the existence and location of any known or presumed asbestos containing materials (“ACM”) within those buildings.

The Council’s governing body has adopted the Council’s corporate [asbestos-registers]Asbestos Policy, which is available on our website.

The registers and plans are in two forms. First, the Council maintains a corporate asbestos register and a corporate asbestos management plan. Second, the Council has prepared individual registers and individual plans for each building that contains or may contain ACM. Hardcopies of those individual registers and plans are held in the building concerned.

Whenever work is carried out on a Council building the hardcopy register and the hardcopy plan are each amended by hand, as required. This action ensures that Council employees or contractors who work from time to time within that building have access to accurate information about the ACM that it contains or may contain.

The electronic versions of each of the corporate plans and registers, and of the plans and registers for individual buildings, are periodically updated. However, the key documents are the hardcopy registers and the hardcopy plans for each building which must be inspected before any work is carried out on that building.

NOTES:

- (1) The Council’s electronic registers and plans are valid as dated, and ARE NOT to be relied upon as definitive records and ARE NOT to be used for reference purposes for any construction, demolition, maintenance or any other onsite works. IN ALL CASES, the onsite hardcopy building specific asbestos register and building specific asbestos management plan MUST BE CONSULTED prior to the commencement of physical works on the building concerned. While the electronic versions of the Council’s registers and plans provide guidance concerning the presence or possible presence of ACM it is the onsite hardcopy registers and plans which will remain up to date.
- (2) The Council’s electronic registers and plans relate to Council owned or managed buildings. The electronic registers and plans do not relate to structures (such as picnic shelters, bus shelters and other freestanding structures). Before any work is carried out on such structures the Council’s Hazardous Materials Team (“HMT”) MUST BE CONSULTED. The HMT may be contacted at council@bmcc.nsw.gov.au. The HMT will provide information concerning any ACM that may be present in the structure concerned.

Further information: Further information on safe asbestos management may be obtained by contacting Councils Hazardous Materials Management Team at council@bmcc.nsw.gov.au.



Report

ASBESTOS REGISTER

**Blue Mountains City
Council – August 2017**

**Prepared for:
Blue Mountains City
Council**

**Project No.
37272**

**Date:
26-09-17**

The logo for AIRSAFE, featuring the word "AIRSAFE" in white, bold, uppercase letters on a dark blue rectangular background.

93 Beattie Street
Balmain NSW 2041 Australia
T. 02 9555 9034
F. 02 9555 9035
info@airsafe.net.au
www.airsafe.net.au

ABN 36 609 424 946

DISTRIBUTION

Copies	Recipient
2	Richard Kane-White Blue Mountains City Council Strategic Assets Officer Locked Bag 1005 KATOOMBA NSW 2780

© Airsafe OHC Pty Limited [Airsafe]

The information contained in this document is intended for the sole use of the Client identified on the cover sheet for the purpose for which it has been prepared. Airsafe undertakes no duty to or accepts any responsibility for any third party who may rely upon this document.

All rights reserved. No section or element of this document may be removed, reproduced, electronically stored or transmitted in any form without the written permission of Airsafe.

Prepared By:



Ashley McDonald
[SafeWork NSW Licence No LAA 001261]

Reviewed By:



Simon Gorham
Manager

3.1.18 – Glenbrook Park – Great Western Highway, Glenbrook.....	34
3.1.19 – Knapsack Clubhouse – 31 Great Western Highway, Glenbrook.....	36
3.1.20 – Hawkesbury Heights Public Toilet Block – 847-1013 Hawkesbury Road, Hawkesbury Heights	37
3.1.21 – S.E.S. Store Building – 224A Great Western Highway, Hazelbrook	39
3.1.22 – 21 Lester Avenue, Hazelbrook	39
3.1.23 – 193 Great Western Highway, Hazelbrook	40
3.1.24 – 2-16 Cemetery Road, Katoomba.....	41
3.1.25 – 2-6 Civic Place, Katoomba	41
3.1.26 – Visitor’s Information Centre – 46A Echo Point Road, Katoomba	42
3.1.27 – Bureau Park – Mistral and Barton Street, Katoomba	43
3.1.28 – 90 Cliff Drive, Katoomba	44
3.1.29 – Katoomba Scout Hall – 17 Dora Street, Katoomba	44
3.1.30 – Echo Point Road, Katoomba	45
3.1.31 – Gang Gang Street, Katoomba.....	46
3.1.33 – Katoomba Falls Road, Katoomba	47
3.1.34 – 152-154 Katoomba Street, Katoomba.....	48
3.1.35 – Panorama Drive, Katoomba	49
3.1.36 – 2-38 South Street, Katoomba.....	50
3.1.37 – 17 Station Street, Katoomba	51
3.1.38 – 32 – Hinkler Park – 42 Warialda Street, Katoomba.....	53
3.1.39 – Katoomba Falls Caravan Park – 101B Cliff Drive, Katoomba	54
3.1.40 – 10 Station Street, Katoomba	57
3.1.41 – SES – 3-9 Valley Road, Katoomba	59
3.1.42 – Katoomba Golf Club – 1 – 51 Acacia Street, Katoomba	60
3.1.43 – Waste Management Facility – 49 – 89 Woodlands Road, Katoomba	64
3.1.44 – Explorers Road, Lapstone.....	66
3.1.45 – Lawson Council Building and Library – 5-7 Loftus Street, Lawson	68
3.1.46 – Heatherbrae House – 1 Benang Street, Lawson.....	70
3.1.47 – Lawson Swimming Pool – 2-16 St Bernards Drive, Lawson	72
3.1.48 – Leura Cascades – Cliff Drive – Leura	75
3.1.49 – Carpark – Megalong Street, Leura	76
3.1.50 – 151-153 Sublime Point Road, Leura	77
3.1.51 – 53-55 Olympian Parade, Leura	77
3.1.52 – Burke Road, Linden.....	78
3.1.53 – 201 Megalong Road, Megalong Valley	79

The control measures required for identified and presumed ACM should be determined from the risk assessment and should follow the following principles:

- Control Measure 1 -** If the ACM are friable and not in a stable condition, and there is a risk to health from exposure, they should be removed by an asbestos removalist as soon as practicable.
- Control Measure 2 -** If the ACM are friable but are in a stable condition and are accessible, serious consideration should be given to their removal. If the removal is not immediately practicable, short-term control measures, such as sealing and enclosure, May be able to be used until removal is possible.
- Control Measure 3 -** If the ACM are not friable and are in a good, stable condition, minimising disturbance and encapsulation may be appropriate controls.
- Control Measure 4 -** Any remaining ACM should be clearly labeled, where possible, and regularly inspected to ensure they are not deteriorating or otherwise contributing to an unacceptable health risk.

These control measures reflect the following hierarchy of controls:

- 1 - Elimination/removal (most preferred);
- 2 - Isolation/enclosure/sealing;
- 3 - Engineering controls;
- 4 - Safe Work Practices (administrative controls); and
- 5 - Personal Protective Equipment (PPE) (least preferred).

ACM need to be removed before demolition, partial demolition, renovation or refurbishment if they are likely to be disturbed by those works in accordance with the Code of Practice: How to Safely Remove Asbestos [Safe Work Australia, 2011].

3.1.49 – Carpark – Megalong Street, Leura

Location	Material	Sample ID	Sample Status	Photo No.	Asbestos Classification	Condition	Accessibility	Re-inspect	Current Label	Control Measure	Record of Works Undertaken
E00499 – Toilet Block											
Internal											
Ceiling linings 3263	Fibreboard	37272-72	Negative	-	-	-	-	-	-	-	-
Cubicle partitions 3264	Fibreboard	37272-73	Negative	-	-	-	-	-	-	-	-

APPENDIX A – ANALYSIS RESULTS



93 Beattie Street Balmain NSW 2041 Australia
T. 02 9555 9034 | F. 02 9555 9035
info@airsafe.net.au | www.airsafe.net.au
93 Beattie Street Balmain NSW 2041 Australia
T. 02 9555 9034 | F. 02 9555 9035
info@airsafe.net.au | www.airsafe.net.au
ABN 36 609 424 946

TEST REPORT

September 26, 2017

Blue Mountains City Council
Locked Bag 1005
KATOOMBA NSW 2780

Your Reference: Blue Mountains City Council - August 2017
Job Number: 37272

Attention: Richard Kane-White

Dear Richard,

In accordance with your instructions, Airsafe tested samples from the above site for asbestos content.

The following samples were processed on the dates indicated.

Samples:	131 Samples
Date of Sample Receipt:	21/08/17 – 28/10/17
Date of Sample Analysis:	21/08/17 – 28/10/17
Date of Preliminary Report Sent:	Not Issued

The results are contained in the following pages of this report.

Should you have any queries regarding this report please contact the undersigned.

Yours faithfully
AIRSAFE OHC PTY LTD

Benjamin Willetts
Approved Identifier and Signatory



Accredited for compliance with ISO/IEC 17025 – Testing.
NATA accredited laboratory 2959.
This report must not be reproduced except in full.
Accredited for compliance with ISO/IEC 17025.
NATA accredited laboratory 2959.
This report must not be reproduced except in full.

37272 – 69	E00133 – Toilet Block - Lawson Swimming Pool – 2-16 St Bernards Drive, Lawson - Tank room – Cement tanks x3	5x5x2mm fibrous cement sheet fragment	Chrysotile asbestos detected
37272 – 70	E00133 – Toilet Block - Lawson Swimming Pool – 2-16 St Bernards Drive, Lawson - Main inlet pipe. Continues underground after valve and polyurethane pipe – North of swimming pool	5x5x2mm fibrous cement sheet fragment	Chrysotile asbestos detected Amosite asbestos detected
37272 – 71	E00521 – Shelter Shed 4 (North) - Lawson Swimming Pool – 2-16 St Bernards Drive, Lawson – Wall cladding	10x10x2mm fibreboard fragment	No asbestos detected Organic fibres detected
37272 – 72	E00499 – Toilet Block - Carpark – Megalong Street, Leura - Ceiling linings	10x5x1mm fibreboard fragment	No asbestos detected Organic fibres detected
37272 – 73	E00499 – Toilet Block - Carpark – Megalong Street, Leura – Cubicle partitions	10x2x1mm fibreboard fragment	No asbestos detected Organic fibres detected
37272 – 74	NAN200 – Linden Rural Fire Service Bushfire Station - 53-55 Olympian Parade, Linden - Male bathroom – Wall cladding	10x4x1mm fibreboard fragment	No asbestos detected Organic fibres detected
37272 – 75	E00061 – Toilet Block (On Left 400m Past Old Sawmill On Right Side) - 201 Megalong Road, Megalong Valley - Men’s bathroom – Ceiling lining	20x20x3mm fibrous cement sheet fragment	Chrysotile asbestos detected
37272 – 76	E00197 – Toilet Block - 12-14 The Avenue, Mount Wilson – Wall cladding	10x10x2mm fibreboard fragment	Chrysotile asbestos detected Organic fibres detected
37272 – 77	E00116 – Toilet Block (Beside Public Hall) - Calver Avenue, Mount Riverview - Bathroom – Ceiling lining	5x3x3mm fibreboard fragment	Chrysotile asbestos detected
37272 – 78	Asset D00100 – Pavilion Building - 92A Great Western Highway, Mount Victoria - Ceiling lining	5x3x2mm fibreboard fragment	No asbestos detected Organic fibres detected
37272 – 79	Asset E00207 – Toilet Block – 92A Great Western Highway, Mount Victoria - Women’s bathroom – Toilet partition walls	10x3x2 fibreboard fragment	No asbestos detected Organic fibres detected
37272 – 80	E00252 – Toilet Block - 389-407 Great Western Highway, Springwood - Disabled bathroom – Ceiling lining	5x5x1mm fibreboard fragment	No asbestos detected Organic fibres detected
37272 – 81	E00251 – Toilet Block - 389-407 Great Western Highway, Springwood - Fragments under switchboard	40x30x5mm fibrous cement sheet fragment	Chrysotile asbestos detected Amosite asbestos detected
37272 – 82	Asset E00545 – Plumbers Workshop/ General Gangs Store/ Attached Lunch Room - 2-20 Lawson Road, Springwood – Wall cladding	25x20x5mm fibreboard fragment	No asbestos detected Organic fibres detected
37272 – 83	Asset E00545 – Plumbers Workshop/ General Gangs Store/ Attached Lunch Room - 2-20 Lawson Road, Springwood – Internal wall cladding	15x10x2mm fibreboard fragment	No asbestos detected Organic fibres detected
37272 – 84	E00548 – Painters Workshop - 2-20 Lawson Road, Springwood - Redundant cement pipes at rear x 2	40x25x5mm fibreboard fragment	No asbestos detected Organic fibres detected
37272 – 85	Asset NAN113 – Red Cross Hall - 101-105 Macquarie Road, Springwood - Awning adj.	8x3x1mm fibreboard fragment	No asbestos detected Organic fibres detected



Accredited for compliance with ISO/IEC 17025 – Testing.
NATA accredited laboratory 2959.
This report must not be reproduced except in full.

Accredited for compliance with ISO/IEC 17025.
NATA accredited laboratory 2959.
This report must not be reproduced except in full.

APPENDIX C – WARNING SIGNS AND LABELS

